Get help if you're struggling with living costs

Find out what support is available and any unclaimed benefits you're entitled to.

White Hart junction

White Hart Junction is a key gateway into Swindon, connecting the A420 with the A419. The new slip road provides a safer and quicker connection to the M4 and A419. Work was carried out to improve safety, provide additional capacity, and mitigate the impact of the New Eastern Villages (NEV) development to cope with current traffic and accommodate additional traffic generated by the NEV Development in this area of the town. In its previous form, the White Hart junction was operating at near capacity and would not have coped with the predicted future traffic flows.

External funding was awarded from the Department of Transport (DfT) and Local Growth Fund (LGF). The total amount of funding awarded to this scheme is £29m and the remaining £1m will be obtained from developers' contributions (S106).

What work was completed?

Traffic signals were added at the White Hart roundabout and a new northbound slip road on to the A419 ws built. This replaced the old slip road

on Merlin Way which was not up to current design standards. A new bridge over the railway was built to accommodate this.

The southbound slip road from the A419 on to the White Hart roundabout was widened. The old entry point off White Hart junction on to Ermin Street was closed and replaced with a new section of road and priority junction off Oxford Road. There is now an increase in the number of lanes on the roundabout and the existing footbridge was retained.

Noise pollution and mitigation measures have been considered within the detailed design of White Hart junction. As part of the scheme, the council's design engineers will undertake noise monitoring before and after the scheme is delivered and this study will form the basis of mitigation measures.

You can view a detailed map and 3D illustration of what the junction will look like in the documents below:

- **White Hart junction plan** (PDF)
- **White Hart junction 3D illustration** (PDF)

In addition, the following video shows a flythrough of the White Hart junction:

When will the work be done?

Work began on the railway in October 2019 and work on the carriageway started in Spring/Summer 2020.

The new northbound A419 sliproad opened to traffic in March 2022. Traffic signals will start to be operational on 9 May and will be monitored in conjunction with the Gablecross lights once they become operational towards the end of May 2022.

The whole project is expected to be completed by end of May 2022.

Give feedback about this page

© 2022 Swindon Borough Council
Powered by **Jadu**