Planting Schedule

Trees

Number	Abbreviation	Species	Specification	Height	Pot Size	Girth	Density
15	Ace cam Els	Acer campestre 'Elsrijk'	Extra Heavy Standard; Clear Stem 175-200; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
14	Ace cam S	Acer campestre 'Streetwise'	Extra Heavy Standard; Clear Stem 175-200; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
6	Ain inc A	Alnus incana 'Aurea'	Extra Heavy Standard; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
7	Ame arb R H	Amelanchier arborea Robin Hill	Select Standard; Clear Stem 150-175; 5 breaks; 3x	300-350cm	RB	10-12cm	Counted
11	Bet erm	Betula ermanii	3x; Extra Heavy Standard; clear stem minimum 200cm; 5 breaks	400-450cm	RB	14-16cm	Counted
10	Car bet F F	Carpinus betulus 'Frans Fontaine'	Extra Heavy Standard; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
5	Lig luc	Ligustrum lucidum	Select Standard; 4 breaks; 3x	300-350cm	RB	10-12cm	Counted
14	Liq sty	Liquidambar styraciflua	Extra Heavy Standard; Clear Stem 175-200; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
16	Pru S	Prunus 'Spire'	Select Standard; 5 breaks; 3x	300-350cm	RB	10-12cm	Counted
3	Que rob	Quercus robur	Extra Heavy Standard; Clear Stem 175-200; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
4	Sor arI L	Sorbus aria 'Lutescens'	Select Standard; 5 breaks; 3x	300-350cm	RB	10-12cm	Counted
1	Sor auc S S	Sorbus aucuparia 'Sheerwater Seedling'	Extra Heavy Standard; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted

Total :106

Specimen Shrubs

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
1	Cho ter 'Sun'	Choisya ternata 'Sundance'	Bushy; 7/10 breaks	60-80cm	20L	Counted
27	Heb M W	Hebe 'Mrs Winder'	Bushy; 9 breaks	40-60cm	10L	Counted
8	Hyd mac M	Hydrangea macrophylla 'Mariesii'	Branched; 7 breaks	60-80cm	10L	Counted
11	Hyd mac V	Hydrangea macrophylla 'Veitchii'	Branched; 5 breaks	40-60cm	5L	Counted
17	Pot tru P B	Potentilla fruticosa 'Princess Betty'	Bushy; 7 breaks	N/A	10L	Counted
11	Pyr O G	Pyracantha 'Orange Glow'	Carried; leader with laterals; 6 breaks	125-150cm	10L	Counted
6	Ski jap R	Skimmia japonica 'Rubella'	Bushy; 7 breaks	40-60cm	15L	Counted
5	Syr mey P	Syringa meyeri 'Palibin'	Bushy; 5 breaks	40-60cm	10-15L	Counted

Total :87

Shrubs

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
42	Auc jap	Aucuba japonica	Bushy; 3 breaks	40-60cm	5L	3/m²
113	Auc jap R	Aucuba japonica 'Rozanne'	Bushy; 4 breaks	30-40cm	5L	3/m²
51	Ber thu H	Berberis thunbergii 'Harlequin'	Branched; 5 breaks	40-60cm	5L	4/m²
24	Bra S	Brachyglottis 'Sunshine'	Branched; 6 breaks	40-60cm	5-7.5L	3/m²
11	Cho ter S	Choisya ternata 'Sundance'	Bushy; 5 breaks	40-60cm	5L	3/m²
135	Cor alb E	Cornus alba 'Elegantissima'	Bushy; 4 breaks	40-60cm	3L	3/m²
55	Cor san	Cornus sanguinea	1 + 1 Transplant-seed raised; branched; 3 breaks	60-80cm	BR	3/m²
90	Cyt bos Z	Cytisus × boskoopii 'Zeelandia'	Bushy; 7 breaks	40-60cm	3L	4/m²
49	Dap ode A	Daphne odora 'Aureomarginata'	Branched; 3 breaks	30-40cm	2L	3/m²
8	Ela ebb L	Elaeagnus ebbingei 'Limelight'	Branched; 4 breaks	40-60cm	5L	4/m²
14	Euo for B	Euonymus fortunei 'Blondy'	Bushy; 9 breaks	N/A	5-7.5L	3/m²
130	Euo for E Go	Euonymus fortunei 'Emerald 'n' Gold'	Bushy; 9 breaks	N/A	5-7.5L	3/m²
33	Euo for E G	Euonymus fortunei 'Emerald Gaiety'	C. 3/6 breaks; Bushy;			4/m²
262	Euo for S Q	Euonymus fortunei 'Silver Queen'	Bushy; 9 breaks	N/A	5-7.5L	3/m²
11	Euo for S	Euonymus fortunei 'Sunspot'	Bushy; 9 breaks	30-40cm	10L	4/m²
75	Euo jap B	Euonymus japonicus 'Bravo'	Bushy; 4 breaks	40-60cm	5L	3/m²
281	Heb A G	Hebe 'Autumn Glory'	Bushy; 7 breaks	30-40cm	5L	3/m²
17	Heb A G	Hebe 'Autumn Glory'	C. 3/6 breaks; Bushy;		3L	3/m²
75	Heb 'G O'	Hebe 'Great Orme'	C. 3/5 breaks; Bushy;	25-30cm	3L	3/m²
56	Heb 'G O'	Hebe 'Great Orme'	C. 3/5 breaks; Bushy;	20-30cm	3L	4/m²
57	Heb R E	Hebe 'Red Edge'	Bushy; 7 breaks	N/A	5-7.5L	3/m²
76	Heb alb 'R E'	Hebe albicans 'Red Edge'	Bushy; 7 breaks	N/A	5-7.5L	4/m²
88	Heb bra W G	Hebe brachysiphon 'White Gem'	Bushy; 5 breaks	30-40cm	5L	3/m²
90	Heb rak	Hebe rakaiensis	Bushy; 7 breaks	N/A	5-7.5L	4/m²
72	Hyd mac W W	Hydrangea macrophylla 'White Wave'	Branched; 5 breaks	40-60cm	5L	3/m²
113	Hq	Hydrangea quercifolia	Branched; 3 breaks	40-60cm	5L	3/m²
135	Hyd ser B	Hydrangea serrata 'Bluebird'	Branched; 3 breaks	30-40cm	3L	3/m²
94	Ker jap	Kerria japonica	Branched; 5 breaks	40-60cm	3L	3/m²
79	Lav ang L P	Lavandula angustifolia 'Loddon Pink'	Bushy; 5 breaks	30-40cm	5-7.5L	3/m²
47	Lav ang M	Lavandula angustifolia 'Munstead'	Bushy; 7 breaks	30-40cm	5-7.5L	3/m²
49	Lav ang R	Lavandula angustifolia 'Rosea'	Bushy; 7 breaks	20-30cm	5L	4/m²
42	Leu wal R	Leucothoe walteri 'Rainbow'	Bushy; 5 breaks	30-40cm	5L	3/m²
91	Lig vul	Ligustrum vulgare	0/2; Cutting; branched; 3 breaks	60-80cm	BR	3/m²
42	Lon nit M G	Lonicera nitida 'May Green'	Bushy; 8 breaks	N/A	5L	3/m²
75	Nan dom F P	Nandina domestica 'Fire Power'	Bushy; 6 breaks	N/A	5L	4/m²
40	Phi B E	Philadelphus 'Belle Etoile'	Branched; 7 breaks	60-80cm	10L	3/m²
64	Pho fra L R R	Photinia fraseri 'Little Red Robin'	Bushy; 6 breaks	30-40cm	3L	3/m²
88	Pit ten T T	Pittosporum tenuifolium 'Tom Thumb'	Bushy; 3 breaks	10-20cm	5L	3/m²
266	Pru lau O L	Prunus laurocerasus 'Otto Luyken'	Bushy; 5 breaks	40-60cm	5-7.5L	3/m²
57	Ros off	Rosmarinus officinalis	Bushy; 5 breaks	40-60cm	5L	3/m²
55	Sam nig	Sambucus nigra	1+1 Transplant-seed raised; branched; 3 breaks	60-80cm	BR	3/m²
14	Sar con	Sarcococca confusa	Bushy; 6 breaks	30-40cm	5L	3/m²
93	Sar hoo H	Sarcococca hookeriana humilis	Bushy; 7 breaks	25-30cm	7.5L	3/m²
151	Sar hoo d	Sarcococca hookeriana digyna	Bushy; 6 breaks	30-40cm	5L	3/m²
178	Ski con K G	Skimmia confusa 'Kew Green'	Bushy; 4 breaks	30-40cm	5L	3/m²
236	Ski jap R	Skimmia japonica 'Rubella'	Bushy; 4 breaks	30-40cm	5L	3/m²
19	Ski jap R	Skimmia japonica 'Rubella'	Bushy; 7 breaks	40-60cm	15L	3/m²
72	Ski jap V	Skimmia japonica 'Veitchii'	Bushy; 4 breaks	30-40cm	5L	3/m²
65	Spi jap C L	Spiraea japonica 'Candle Light'	Bushy; 6/9 breaks	40-60cm	10L	3/m²
80	Spi jap G	Spiraea japonica 'Goldflame'	Bushy; 5/7 breaks	30-40cm	5-7.5L	3/m²
55	Sym mai	Symphoricarpos albus	0/2; cutting; branched; 3 breaks	60-80cm	BR	3/m²
42	Vib dav	Viburnum davidii	Bushy; 4 breaks	30-40cm	5-7.5L	3/m²
8	Vib opu C	Viburnum opulus 'Compactum'	Bushy; 4 breaks	30-40cm	3L	4/m²
94	Vib pli M	Viburnum plicatum 'Mariesii'	Branched; 3 breaks	40-60cm	3L	3/m²
11	Vib tin E P	Viburnum tinus 'Eve Price'	Bushy; 5/7 breaks	40-60cm	7.5L	3/m²
62	Vin maj V	Vinca major 'Variegata'	Several shoots; 3 breaks	N/A	3L	3/m²
206	Vin min G J	Vinca minor 'Gertrude Jekyll'	Several shoots; 3 breaks		3L	4/m²
52	Wei flo F P	Weigela florida 'Foliis Purpureis'	Branched; 4 breaks	30-40cm	3L	4/m²

Total :4690

Herbaceous

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
114	Ber cor P	Bergenia cordifolia 'Purpurea'	Full pot		3L	3/m²
5	Ger J B	Geranium 'Johnson's Blue'	Full pot		2L	5/m²

Total :119

Grasses

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
51	Bri med	Briza media	Full Pot; Sept to April planting; British native-origin		3L	4/m²
281	Car hac E	Carex hachijoensis 'Evergold'	Full Pot		5L	3/m²
93	Car om V	Carex orrithopoda 'Variegata'	Full Pot		3L	4/m²
14	Fes gla	Festuca ovina glauca	C. Full Pot		3L	3/m²
17	Hak mac A	Hakonechloa macra 'Aureola'	Full Pot		5L	3/m²
56	Sti arc	Stipa arundinacea	Full Pot		3L	4/m²
38	Sti ten P T	Stipa tenuissima 'Pony Tails'	Full Pot		5L	3/m²

Total :550

Conifers

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
58	Pin mug M	Pinus mugo 'Mops'	Bushy	10-20cm	3L	4/m²

Total :58

Hedges

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
483	Cor alb E	Cornus alba 'Elegantissima'	Branched; 4 breaks	60-80cm	5L	0.45Ctr Double Staggered at 0.35m offset
947	Esc D R	Escallonia 'Donard Radiance'	Bushy; 5 breaks	40-60cm	5L	0.45Ctr Double Staggered at 0.3m offset
367	For int L	Forsythia intermedia 'Lynwood'	Branched; 5 breaks	60-80cm	5-7.5L	0.45Ctr Double Staggered at 0.35m offset
165	Lig vul	Ligustrum vulgare	0/2; Cutting; branched; 3 breaks	60-80cm	BR	0.4Ctr Double Staggered at 0.3m offset
367	Pho fra R R	Photinia fraseri 'Red Robin'	Branched; 6 breaks	40-60cm	5-7.5L	0.45Ctr Double Staggered at 0.35m offset
196	Spi A	Spiraea 'Arguta'	Branched; 7 breaks	60-80cm	10L	0.45Ctr Double Staggered at 0.3m offset

Total :2525

Native Hedge Mix

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
60	Ace cam	Acer campestre	1+2; Transplant - seed raised; BR	100-125cm		0.45Ctr Double Staggered at 0.35m offset
60	Cor ave	Corylus avellana	1+2; Transplant - seed raised; branched; 4 breaks; BR	80-100cm		0.45Ctr Double Staggered at 0.35m offset
240	Cra mon	Crataegus monogyna	1+2; Transplant - seed raised; BR	80-100cm		0.45Ctr Double Staggered at 0.35m offset
60	Ile aqu	Ilex aquifolium	Leader with laterals	60-80cm	5L	0.45Ctr Double Staggered at 0.35m offset
31	Ros can	Rosa canina	1+1; Transplant - seed raised; branched; 3 breaks; BR	60-80cm		0.45Ctr Double Staggered at 0.35m offset
60	Cor san	Cornus sanguinea	1+2; Transplant - seed raised; branched; 4 breaks; BR	80-100cm		0.45Ctr Double Staggered at 0.35m offset
31	Lon per	Lonicera periclymenum	C. 3/6 links; Several Shoots; Carried	80-100cm	3L	0.45Ctr Double Staggered at 0.35m offset
60	Que rob	Quercus robur	C. Whip; Branched; 3/5 breaks;			0.45Ctr Double Staggered at 0.35m offset

Total :602

Hedge Mix

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
76	Ber thu	Berberis thunbergii	1+2; Transplant - seed raised; branched; 3 breaks; BR	60-80cm	BR	0.45Ctr Double Staggered at 0.35m offset
150	Car bet	Carpinus betulus	1+1; Transplant - seed raised; BR	60-80cm	BR	0.45Ctr Double Staggered at 0.35m offset
175	Cor ave	Corylus avellana	1+2; Transplant - seed raised; branched; 3 breaks; BR	60-80cm	BR	0.45Ctr Double Staggered at 0.35m offset
100	Pru pad	Prunus padus	1+1; Transplant - seed raised; BR	60-80cm	BR	0.45Ctr Double Staggered at 0.35m offset

Total :501

Bulb Mix

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
253	Cro chr B P	Crocus chrysanthus 'Blue Pearl'	Grade 5/6			12/m²
253	Cro chr C B	Crocus chrysanthus 'Cream Beauty'	Grade 5/6			12/m²
253	Cro tom R G	Crocus tommasinianus 'Ruby Giant'	Grade 5/6			12/m²
336	Gal niv	Galanthus nivalis	Grade 5/6			12/m²
336	Nar B C	Narcissus 'Bridal Crown'	Grade 5/6			12/m²
253	Nar C	Narcissus 'Canaliculatus'	Grade 5/6			12/m²

Total :1684

© this drawing and the building works depicted are the copyright of **idp** and may not be reproduced or amended except by written permission, no liability will be accepted for amendments made by other persons.

all dimensions to be checked on site and landscape architect notified of any discrepancies prior to commencement.
do not scale.

NOTES:

1.0 Do not scale from drawing, use figured dimensions only
1.1 This drawing to be read in conjunction with all other IDPL drawings and specifications
1.2 Information shown on these drawings is not valid for Construction. Please refer to the status of the drawing in the Title and Issue box
1.3 Do not procure or manufacture materials, or undertake construction site works from this drawing unless the issue status is noted as 'for construction'.
1.4 Any contractor that chooses to take forward this information for construction without full review process and sign-off does so at their own risk.
1.5 All measurements are to be checked on site prior to construction.
1.6 Where any conflict or inconsistency occurs between drawing and specification information the Contractor is to immediately notify IDPL prior to continuing working.
1.7 Information to be read in coordination with Structural Engineer & M&E Engineer drawings & spec; Where any conflict or inconsistency occurs between IDPL and Engineers drawing and specification information the Contractor is to immediately notify IDPL prior to continuing working.
1.8 Proposed drainage runs to be located within adoptable road carriageway and/or hardstanding where possible, please refer to separate drainage design.

PLANTING NOTES
General

1. All planting and operations should comply with the latest version of BS 4428 'General Landscape Operations' and BS 3936 'Nursery Stock - Specification for Trees & Shrubs'.

2. All plants shall be supplied in accordance with the HTA National Plant Specification and from a HTA certified nursery, and in accordance with CPSE Code of Practice for 'Handling and Establishing Landscape Plants, Parts I, II and III.

3. All existing trees and hedges shall be surveyed and protected in accordance with BS 5837:2012, and temporary protection fencing erected for the duration of the construction period. Refer to arboricultural consultants drawings for location and details.

4. Specification of species, position and density shall be in accordance with drawing and planting schedule provided, and should not be amended without prior approval of the Landscape Architect. For detailed landscape specification information, please refer to the relevant documentation accompanying this drawing.

Ground conditional Topsoil

5. All topsoil areas should be clear of rocks and rubble larger than 50mm diameter and any other debris that may interfere with the establishment of plants.

6. Imported topsoil to be multi-purpose grade and free of all contaminants, in accordance with the latest version of BS 3882:2015 Specification for Topsoil. Topsoil analysis should be undertaken and reported, with recommendations for improvements if below the standard for general landscape purposes.

7. Minimum topsoil depths should be as follows unless specified otherwise. Suitable (loosened) subsoil should provide the remainder of the rooting depths as required, and mixed with peat-free compost. Subsoil preparation shall be in accordance with BS 8601 and BS 4428 and scarified /ripped to a suitable depth prior to spreading of topsoil. Any weed/grass growth to be sprayed with appropriate herbicide at least 10 days prior to cultivation:
   - Ornamental shrubs 450mm;
   - native shrubs 300mm;
   - seeded grass 150mm;
   - wildflower grass 50mm, or directly into existing ground;
   - tree pits to be excavated as per details.

Cultivation

8. Planting outside the usual October-March dormant season shall be pursued by approval only. If agreed all bare root plants shall be substituted with container grown stock, with additional establishment watering.

9. Plants shall be bedded in a staggered fashion to avoid formal regimented lines at densities indicated in the schedule, except for specimens, which are to planted in locations shown on the drawing. For mixes: shrubs should be planted in groups of 3, 5 or 7 of the same specification, perennials & grasses should be planted in groups of 3 to 6. Please note: taller plant species to be planted to the rear with lower species to the front.

10. All planting areas and specimens should be watered in to field capacity immediately after planting and mulched with minimum of 50mm depth of medium grade crushed mulch. Where necessary, plants to be protected with rabbit fence and/or individual rabbit guard securely fixed to timber stakes.

Trees & Foundations

11. All trees to be supplied, planted and established in accordance with BS 8545. Trees adjacent to buildings and services shall include root barriers where necessary and should be planted in positions as indicated on the drawings.

12. All foundation designs provided by the architect/engineer must consider the effect of existing trees, and the proposed landscape scheme in accordance with the NHBC Standards. Every effort has been made within the design to follow advice in Chapter 4.2 of the Standards, however landscape proposals should be referred to a structural engineer for checks and any conflicts made known to the Landscape Architect for necessary changes.

13. The contractor is responsible for checking locations of all existing and proposed services, and shall advise the Landscape Architect if there are any conflicts.

14. Trees within hardstanding or highways visibility splays shall be clear stem to 2m high unless specified otherwise.

Maintenance

15. Management operations for the site shall be carried out as detailed in the agreed maintenance schedules at regular intervals, in accordance with any agreed Landscape Management Plan.

16. Any tree or plant which, within a period of 5 years from the implementation, dies, is removed or becomes seriously damaged or diseased, shall be replaced in the next planting season with another of a similar size and species unless otherwise agreed with the Local Planning Authority.

17. Tree Pits

18. Tree pits in soft areas only are estimated based on areas shown on plan multiplied by tree pit depth (0.9m) with allowances for wall foundations and kerb build ups as appropriate. Tree pits with supplementary root space soil cells are estimated based on areas shown on plan in soft areas multiplied by tree pit depth (0.9m) and areas under hard surfaces multiplied by soil cell depth (0.4m).

- Application boundary
- Existing vegetation retained
- Lawn: Amenity (Rolawn Medallion Grass)
- Lawn: Flowering (Low flowering lawn seed mix; wildflowerlawnsandmeadows.com; 5g/m2)
- Meadow: Wildflower (EM2 Standard General Purpose Meadow Mixture; 5g/m2)
- Meadow: Woodland Edge (Emorsgate EH1 - EH1 Hedgerow Mixture, 5g/m2)
- Proposed trees
- Proposed hedges
- Proposed shrub planting
- Proposed areas of gravel
- Seating (Bench - Preva Urbana Park by mmcite or similar)
- Pathway (Breedon gravel or similar)
- Extent of below surface tree pits (GreenBlue Urban Root Space Systems, refer to details)

rev.	date:	comment(s):	drawn:	check:
D	07.11.24	Updated to latest layout. Note added re: visibility splays	EC	EC
C	22.10.24	Note added re: tree loss mitigation	EC	EC
B	10.10.24	Updated to latest layout & planning comments	DM	EC
A	06.08.24	Retained / removed hedgerows amended	DM	EC

IDP ARCHITECTURE
URBAN DESIGN & MASTERPLANNING
LANDSCAPE & ENVIRONMENT

status: Planning RIBA Stage: 4
client: Vistry Group
job: R6 R7 Woodlands, South Marston
title: Soft Landscape Proposals General Arrangement
drawn: DM date: 31.07.24
checked: EC scale @ a1: 1:500
drwg no: IDPL LA5979-BP-400 rev: D

IDP GROUP 27 SPON STREET COVENTRY CV1 3BA
T: **+44 (0)24 7652 7600** E:info@idpgroup.com
www.weareidp.com