Health & Safety - CDM Regulations 2015 (Design Risk)

The following risks have been identified for which a suitably qualified and experienced street lighting contractor holding a 'HERS' certificate would be familiar with and should therefore be used for installation, maintenance and decommissioning. A comprehensive risk assessment should be carried out prior to the commencement of any site work.

1. Underground Services
   This design has not included a survey of existing and proposed underground services, the owners of these services must be consulted prior to commencement of works.
   Electricity
   Gas
   Water/Sewage
   Telecoms

2. Overhead cables
   Removal of lighting equipment to comply with G39 regulations.

3. Working near a public highway
   Columns should be installed with the doors orientated such that an operative working in the base compartment faces oncoming traffic. Appropriate traffic management must be used for any works on these column.

4. Working with electricity
   Compliance with local DNO/IDNO regulations.

5. During works all traffic management to be in accordance with Chapter 8 of the traffic signs manual.

Drawing to be read in conjunction with:

- Lighting Schedule (Ref 800/101)
- Swindon Borough Council developers specification

Street Lighting Key:

Proposed 6m CU Phosco tubular steel hot dip galvanised column with root protection, finish to SBC specification. M10 Hex lock (SL2). Column to receive a post top mounted lantern manufactured by Urbis Axia 3.2 (RAL 9002 Grey White) 5295 32 LED 600mA 441022 7.84klm WW, complete with 7 Pin NEMA socket and GPS enabled Telensa node Product code T2E1N-G3.
Rear shields to be installed where stated by the developer.
Lanterns to be set to 0 deg. tilt. Charles endirect or Lucy double pole locakable BS88 fused isolator (4A) to be mounted above the DNO cut out. All columns to be energised by DNO/IDNO. Refer to DNO/IDNO electrical design for connection and cabling details.
Project quantity (21no.)

LC1-1 Column number

Isolux Contour - 1.0 Lux

Notes:

1. Any alterations to the positions of columns and associated equipment shown on this drawing must be referred to the designer to ensure compliance with lighting level requirements before installation.
2. Setting out should be conducted by a competent person. Before construction, Swindon Borough Council should be notified for agreement/inspection if required. It is advised that SBC approved contractors are to be commissioned to install lighting equipment. Tree and hedge clearing may be required to locate column.
3. Columns to be planted at back of footpath.
4. Column doors to face away from the traffic flow.
5. Ensure the correct orientation of lantern to road kerb line as detailed within the drawing.
6. Column numbering as detailed on the drawing is for reference only. Upon completion of installation prior to adoption, the contractor must submit an as-built drawing to SBC Lighting Engineer for numbering detail. Numbers to be affixed to columns in accordance with SBC specification.
7. The contractor is responsible for placing all orders for disconnections and new connections to adoptable road lighting columns and associated illuminated equipment. The contractor is liable for all power charges up to adoption hand over
8. Upon completion of works, full electrical test certificates are to be presented to SBC Lighting Engineer.
9. This lighting design has been completed with reference to SBC Street Lighting Specification Document. This document and standard detail drawings are available from SBC and should be read in conjunction with this drawing for further equipment and installation guidance. All materials and equipment shall comply with BCC specification. Any alternative materials or equipment proposed by the contractor shall be submitted to SBC for approval before purchase or installation works.
10. Installation works shall also comply with the current issue and amendments of BS7671: 18th edition IEE wiring regulations 2008, requirements for electrical installations, current editions of the ILP code of practice for electrical safety in public lighting operations and the code of practice for the erection of street lighting published by the Association of Street Lighting Electrical Contractors.

Rev	By	Chkd	Apprvd	Date	Description
-	-	-	-	-	-

Client

RAPPOR

Development

SOUTH MARSTON, SWINDON

Drawing

STREET LIGHTING DESIGN (S38)

Drawn by: EDS

Date Drawn: 11.11.2024

Drawing No.

800/001

Revision

-

Drawing Scale: 1:500 at A1