Original Drawing Size A1

KEY:

PROPOSED LEVEL

EXISTING GROUND LEVEL

CHAINAGE ON CENTRELINE (m)	LEVELS ON LEFT HAND CHANNEL (m)	LEVELS ON RIGHT HAND CHANNEL (m)	EXISTING LEVELS (m)
0.000	102.016	102.016	101.873
8.401	102.514	102.514	101.855 101.925
18.401	102.886	102.886	101.491 101.446
26.401	102.856	102.856	101.154 101.085
40.000	102.563	102.563	100.822
50.000	102.310	102.310	100.589
60.000	102.058	102.058	100.311
70.000	101.805	101.805	100.005
80.000	101.553	101.553	99.882
90.000	101.300	101.300	99.767
100.000	101.048	101.048	99.595
110.000	100.795	100.795	99.409
120.000	100.543	100.543	99.281
130.000	100.290	100.290	99.168
140.000	100.038	100.038	99.065
150.000	99.785	99.785	98.973
160.000	99.533	99.533	98.814
170.000	99.280	99.280	98.648
180.000	99.027	99.027	98.573
190.000	98.775	98.775	98.492
200.000	98.522	98.522	98.453
210.000	98.270	98.270	98.431
220.000	98.017	98.017	98.446
230.000	97.765	97.765	98.361
232.064	97.713	97.713	98.260
240.000	97.574	97.574	97.930
242.064	97.558	97.558	97.889
250.000	97.573	97.573	97.739
252.064	97.597	97.597	97.665
260.000	97.706	97.706	97.526
270.000	97.843	97.843	97.384
280.000	97.980	97.980	97.352
290.000	98.117	98.117	97.303

VERTICAL DESIGN ON CARRIAGEWAY CENTRELINE:
- GRADIENT 5.9% L = 8.401m
- HOG CURVE R = 236.298 L = 20.000
- GRADIENT -2.5% (-1 in 40) LENGTH = 203.663m
- SAG CURVE R = 513.293 L = 20.000
- GRADIENT 1.4% (1 in 73) LENGTH = 49.579m

HORIZONTAL DESIGN ON CARRIAGEWAY CENTRELINE:
- STRAIGHT LENGTH = 91.955m
- CURVE R = 650.000 L = 17.541
- STRAIGHT LENGTH = 82.697m
- CURVE R = 54.000 L = 70.537

NOTES:

1. Do not scale from this drawing.
2. All dimensions are in metres unless otherwise stated.
3. Brookbanks consulting ltd has prepared this drawing for the sole use of the client. the drawing may not be relied upon by any other party without the express agreement of the client and Brookbanks consulting ltd. where any data supplied by the client or from other sources has been used, it has been assumed that the information is correct. no responsibility can be accepted by Brookbanks consulting ltd for inaccuracies in the data supplied by any other party. the drawing has been produced based on the assumption that all relevant information has been supplied by those bodies from whom it was requested.
4. No part of this drawing may be copied or duplicated without the express permission of Brookbanks consulting ltd.
5. All dimensions and all levels in metres unless noted otherwise.
6. Any discrepancies noted on site are to be reported to the engineer immediately.
7. Section 278 agreement highway works to carried out in strict accordance with Swindon Borough council's requirements.
8. All works within existing public highway, including any temporary works or traffic management measures, are subject to the approval of Swindon Borough Council. when works are required on the public highway, the contractor shall liaise with and obtain all statutory approvals from Swindon Borough Council, before commencing these works. these approvals include, but are not limited to, approval of traffic management measures, issue of works commencement notices, road opening notices, temporary traffic regulation orders etc.
9. All traffic management shall comply with the requirements as set out in chapter 8 of the traffic signs manual. warning signs may be erected outside the indicated boundaries. any obstructions to traffic or pedestrians shall be properly signed and protected with barriers, cones, signs, and lamps.
10. All planting in visibility splays to be agreed and approved by Swindon Borough Council and in all cases no planting to be above 600mm in height above the carriageway. also no obstructions of any kind within the visibility splay areas.
11. All tactile areas to be laid in accordance with detr "guidance on the use of tactile paving surfaces".
12. All traffic signs and road markings are to be in accordance with the 'Traffic Signs Regulations and General Directions 2016'.
13. Any damage caused to existing footways, roads or other third party property to be made good to the county engineers requirements.
14. Temporary works associated with the construction of the works shall be the responsibility of the contractor.

D	Updated following TW comment 12/04	MA	CM	SM	03.05.24
C	Long-sections updated	MA	CM	SM	09.04.24
B	Key added to long-sections	CM	CM	SM	08.02.23
A	Updated to include under-drained swales	CM	CM	SM	16.01.23
-	First Issue	CM	SM	SM	12.12.22

BROOKBANKS

6150 Knights Court, Solihull Parkway, Birmingham, B37 7WY
T +44 (0)203 958 5400 E mail@brookbanks.com
W brookbanks.com

Swindon EDA Consortium

Proposed Development
Swindon EV

South Marston Primary Street
Long-section Sheet 1 of 5

Status		Status Date
Approval		Dec' 2022
Drawn	Checked	Date
CM	SM	12.12.2022
Scale	Number	Rev
1:500	1335-SMPS-800-103	D

0 10 20 30 40 50
METRES

UNTIL TECHNICAL APPROVAL HAS BEEN OBTAINED FROM THE RELEVANT LOCAL AUTHORITIES, IT SHOULD BE UNDERSTOOD THAT ALL DRAWINGS ARE ISSUED AS PRELIMINARY AND NOT FOR CONSTRUCTION. SHOULD THE CONTRACTOR COMMENCE SITE WORK PRIOR TO APPROVAL BEING GIVEN, IT IS ENTIRELY AT HIS OWN RISK.

© Brookbanks Consulting Limited 2024

P:\1335\CAD\BCL\Current Drawings\S38- South Marston Primary Street\1335-SMPS-800-103-107D South Marston Primary Street Long-Section 1-500.dwg