Transport Planning, Development & Streetworks Management
Wat Tyler West, 5th Floor,
Beckhampton Street,
Swindon, SN1 2JH

Transport Development Management

Memo

To: Planning Services
From: Transport Development Management
Date: 29th June 2022

Application Number: S/COND/21/1998

Proposal: Discharge of condition 6 (Phasing Details) from previous outline permission S/OUT/13/1555.

Location: Land North Of A420 Eastern Villages

Ed,

I refer to the revised submission in relation to the above application.

Condition 6:
Prior to the submission of the first reserved matters application, a phasing plan shall be submitted to and approved in writing by the Local Planning Authority to show how the development shall be implemented in phases. The phasing plan shall include the following elements:
a) The development phases;
b) Major distributor roads/routes within the site, including a defined hierarchy of the road network,
c) Phased access strategy delivery and associated phased housing delivery;
d) Pedestrian / cycle connectivity to committed and emerging parcels of development within the New Eastern Villages;
e) Local centres and community facilities;
f) Strategic foul and surface water features and sustainable drainage systems; and,
g) Strategic landscaping, recreation and open space.
The development shall be carried out in accordance with the approved phasing plan.

Figure B is shown within a landscape A4 document, which is easier to read that the previous Figure 2 in portrait. A number of items are listed within the legend but are not visible on the figure despite being illustrated in other documents. For example, it has been discussed and agreed that a 'Dedicated 3m Cycle track + 2m walkway (5m total)' will be provided along, at least part, of the South Marston Primary Street and Rowborough Primary Street, but this cannot be seen on this figure.

a) The proposed development phases have been illustrated in Figure A, however, both villages have a phase 1 and phase 2, will these phases in the different villages be constructed at the same time? Or will both phases of South Marston be constructed before Rowborough begins, or vice versa.
b) Major distributor roads/routes are not mentioned but Primary and Secondary Streets are. A Northern Loop is proposed within South Marston, but the hierarchy of road here is not clear. No other street types are mentioned. Turning facilities will need to be provided at the end of the loop road during first phases to address the lack of complete provision of the loop road, in accordance with Condition 25 of the outline consent.
c) The phased access strategy and housing delivery, has been more clearly presented within the document but direction of each build is still excluded.

d) Footpath/cycleway provisions are described as provided Dedicated 3m Cycle track + 2m walkway (5m total), Shared cycle track and walk way (3.5) and Secondary footpath 2m, however, as stated above, Figure B does not adequately detail where these routes will be provided.
e) Local centres and community facilities are included in the document but other colleagues will be better placed to comment on their suitability.
f) Please consult our LLFA colleagues on this aspect.
g) Please consult our Landscaping colleagues on this aspect.

Please note that the comments made here represent Officer opinion and cannot be seen to prejudice Swindon Borough Council's formal determination in relation to any application or planning matter.

Alison Curtis
Senior Transport Development Management Engineer

Transport Planning, Development & Streetworks Management
Swindon Borough Council

Email: acurtis@swindon.gov.uk
Tel: 07341 077566
Web: www.swindon.gov.uk