Storm/Foul Outfalls

Refer to wider Infrastructure drawings for storm water discharging into pond and attenuation features together with foul water pump station.

Foul Outfall 1

New Chamber constructed on existing Sewer

Existing Highway Ditch

Flows to be diverted into a new piped system with road gulleys being installed.

Storm Outfall 1

Discharging into Ex. Watercourse

Attenuation Storage Ditch 1500m³

1.2m wide base x 1:3 slope (1.4m design depth)

Flow Control
9.6 l/s discharge rate

Discharging into Ditch

Storm Outfall 2

Discharging into Infrastrucutre Storm Sewer

Foul Outfall 2

Infrastructure Sewers discharging to pump station

Foul Outfall 3

Infrastructure Sewers discharging to pump station

EXISTING BRIDLEWAY RETAINED

BRIDLEWAY CONNECTION

EMERGENCY CONNECTION ONLY

SECONDARY FOOTPATH CONNECTION

FIRE TURNING

3M CYCLE PATH

Old Wanborough Lane

CONSTRUCTION PHASE

Site Safe

SECTION 9:
ENVIRONMENTAL AND WASTE MANAGEMENT

SM09 (01/01/24) Environment and Waste Management Page 1 of 55

Section 9.8 (Silt / Water Management)

Silt Fencing

Careful consideration to extents of topsoil removal

Use of gully bags and terram

REV	DATE	DESCRIPTION	DRAWN
D	12.12.24	Planning Layout Updated	DM
C	24.10.24	Planning Layout Updated	DM
B	26.09.24	Planning Issue	DM
A	29.07.24	Updated to layout amendments	DM

PROJECT Swindon NEV
R8 & R9

TITLE Drainage Strategy

Taylor Wimpey Bristol
Ground Floor
730 Waterside Drive
Aztec West
Almondsbury
Bristol BS33 2AU

T 01454 628400
F 01454 628401
DX 124894 Almondsbury 3

www.taylorwimpey.com

NHBC REG No 76463

Taylor Wimpey

DRN	D Morgan	SCALE	LAND CODE	DRAWING NUMBER	REV
DATE	Jan 24	1:500	20933	101-01	D

Paper Size - ISO A0 (841.00 x 1189.00 MM)
C:\Users\DMorgan\Taylor Wimpey\Bristol Technical Team - Documents\General\cur-site\20933 Skylark, Woodlands, NEV Swindon\03-Design\03-Engineering\101-01-Drainage-Strategy.dwg