DATE:	**6 August 2025**
DESIGNER:	**EDS**
PROJECT No:	**800**
PROJECT NAME:	**South Marston R6/R7 S38 (Rev B)**

LIGHTING REALITY

Designed to BS5489-1:2020 lighting class P4

Rev A - Updated base layout
Rev B - Updated as per SBC comments - 70% dim to applied

Designed value meets P4 Standard Eav = 5.55, Emin = 1.03

Outdoor Lighting Report

Layout Report

General Data

Dimensions in Metres Angles in Degrees
Grid Origin 419608.8m x 187215.4m
Area 268.0m x 285.5m
Sample Spacing 1.50m x 1.49m

Luminaires

Luminaire A Data

Supplier	Urbis Schreder
Type	AXIA 3.1 5266 Integrated lenses 16 OSLO N SQUARE GIANT@500mA
Lamp(s)	16 OSLON SQUARE GIANT@500mA WW 730 230V
LampFlux(klm)/Colour	3.33 WW 3000K/70
File Name	AXIA 3.1 5266 16 OSLON SQUARE GIANT 500mA WW 730 25.8W 429092 Integrated ...
Maintenance Factor	0.83
Imax70,80,90(cd/klm)	1142.4, 192.6, 0.0
No. in Project	24

Layout

ID	Type	X	Y	Height	Angle	Tilt	Cant	Out-reach	Dimmed to	Target X	Target Y	Target Z
1	A	419751.05	187438.25	6.00	145.00	0.00	0.00	0.40	70%			
2	A	419714.47	187421.35	6.00	302.00	0.00	0.00	0.40	70%			
3	A	419699.71	187431.46	6.00	203.00	0.00	0.00	0.40	70%			
4	A	419689.78	187448.02	6.00	207.00	0.00	0.00	0.40	70%			
5	A	419675.49	187470.38	6.00	292.00	0.00	0.00	0.40	70%			
6	A	419676.00	187387.40	6.00	119.00	0.00	0.00	0.40	70%			
7	A	419655.62	187373.25	6.00	31.00	0.00	0.00	0.40	70%			
8	A	419748.20	187418.10	6.00	211.00	0.00	0.00	0.40	70%			
10	A	419768.71	187384.65	6.00	205.00	0.00	0.00	0.40	70%			
12	A	419758.84	187369.73	6.00	125.00	0.00	0.00	0.40	70%			
13	A	419818.21	187383.57	6.00	312.00	0.00	0.00	0.40	70%			
14	A	419782.46	187355.53	6.00	48.00	0.00	0.00	0.40	70%			
15	A	419796.73	187359.61	6.00	307.00	0.00	0.00	0.40	70%			
16	A	419773.55	187333.26	6.00	318.00	0.00	0.00	0.40	70%			
17	A	419814.01	187287.53	6.00	141.00	0.00	0.00	0.40	70%			
18	A	419794.09	187311.03	6.00	231.00	0.00	0.00	0.40	70%			
19	A	419706.54	187290.68	6.00	33.00	0.00	0.00	0.40	70%			
20	A	419731.07	187294.94	6.00	299.00	0.00	0.00	0.40	70%			
19	A	419755.80	187313.55	6.00	318.00	0.00	0.00	0.40	70%			
20	A	419724.21	187360.45	6.00	302.00	0.00	0.00	0.40	70%			

9750800436

Layout Continued

ID	Type	X	Y	Height	Angle	Tilt	Cant	Out-reach	Dimmed to	Target X	Target Y	Target Z
21	A	419668.12	187348.61	6.00	33.00	0.00	0.00	0.40	70%			
22	A	419706.02	187335.49	6.00	121.00	0.00	0.00	0.40	70%			
23	A	419687.97	187316.96	6.00	27.00	0.00	0.00	0.40	70%			
24	A	419691.49	187407.05	6.00	302.00	0.00	0.00	0.40	70%			

DATE: 6 August 2025 DESIGNER: EDS

PROJECT No: 800 PROJECT NAME: South Marston R6/R7 S38 (Rev B)

LIGHTING REALITY

Horizontal Illuminance (lux)

Grid 1

Results

Eav	5.55
Emin	1.03
Emax	19.49
Emin/Emax	0.05
Emin/Eav	0.19

9750800436