Framework Planting Schedule

Trees

Number	Abbreviation	Species	Specification	Height	Pot Size	Girth	Density
11	Ace cam Els	Acer campestre 'Elsrijk'	Extra Heavy Standard; Clear Stem 175-200; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
10	Ace cam S	Acer campestre 'Streetwise'	Extra Heavy Standard; Clear Stem 175-200; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
18	Ame arb R H	Amelanchier arborea Robin Hill	Extra Heavy Standard; Clear Stem 175-200; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
12	Bet erm	Betula ermanii	Extra Heavy Standard; Clear stem minimum 200cm; 5 breaks	400-450cm	RB	14-16cm	Counted
10	Car bet F F	Carpinus betulus 'Frans Fontaine'	Extra Heavy Standard; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
11	Liq sty	Liquidambar styraciflua	Extra Heavy Standard; Clear Stem 175-200; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
13	Mal tri	Malus trioloba	Extra Heavy Standard; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
11	Pru S	Prunus 'Spire'	Extra Heavy Standard; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
2	Pru S B	Prunus 'Sunset Boulevard'	Extra Heavy Standard; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
3	Que rob	Quercus robur	Extra Heavy Standard; Clear Stem 175-200; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
11	Sor arl L	Sorbus aria 'Lutescens'	Extra Heavy Standard; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted
1	Sor auc S S	Sorbus aucuparia 'Sheerwater Seedling'	Extra Heavy Standard; 5 breaks; 3x	425-600cm	RB	14-16cm	Counted

Total :113

Specimen Shrubs

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
1	Cho ter 'Sun'	Choisya ternata 'Sundance'	Bushy; 7/10 breaks	60-80cm	25L	Counted
27	Heb M W	Hebe 'Mrs Winder'	Bushy; 9 breaks	40-60cm	10L	Counted
10	Hyd mac M	Hydrangea macrophylla 'Mariesii'	Branched; 7 breaks	60-80cm	10L	Counted
13	Hyd mac V	Hydrangea macrophylla 'Veluticia'	Branched; 5 breaks	40-60cm	5L	Counted
15	Pot fru P B	Potentilla fruticosa 'Pink Beauty'	Bushy; 7 breaks	N/A	10L	Counted
11	Pyr O G	Pyracantha 'Orange Glow'	Cared; leader with laterals; 6 breaks	125-150cm	10L	Counted
6	Ski jap R	Skimmia japonica 'Rubella'	Bushy; 7 breaks	40-60cm	15L	Counted
5	Syr mey P	Syringa meyeri 'Palibin'	Bushy; 5 breaks	40-60cm	10-15L	Counted

Total :88

Shrubs

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
40	Auc jap	Aucuba japonica	Bushy; 3 breaks	40-60cm	5L	3/m²
96	Auc jap R	Aucuba japonica 'Rozannie'	Bushy; 4 breaks	30-40cm	5L	3/m²
81	Ber thu A N	Berberis thunbergii 'Atropurpurea Nana'	Branched; 4 breaks	20-25cm	3L	3/m²
51	Ber thu H	Berberis thunbergii 'Harlequin'	Branched; 5 breaks	40-60cm	5L	4/m²
27	Bra S	Brachyglottis 'Sunshine'	Branched; 6 breaks	40-60cm	5-7.5L	3/m²
14	Cho ter S	Choisya ternata 'Sundance'	Bushy; 5 breaks	40-60cm	5L	3/m²
129	Cor alb E	Cornus alba 'Elegantissima'	Bushy; 4 breaks	40-60cm	3L	3/m²
77	Cyt bos Z	Cytisus x boskoopii 'Zeelandia'	Bushy; 7 breaks	40-60cm	3L	4/m²
39	Dap odo A	Daphne odora 'Aureomarginata'	Branched; 3 breaks	30-40cm	2L	3/m²
23	Ela ebb L	Elaeagnus ebbingei 'Limelight'	Branched; 4 breaks	40-60cm	5L	4/m²
14	Euo for B	Euonymus fortunei 'Blondy'	Bushy; 9 breaks	N/A	5-7.5L	3/m²
103	Euo for E Go	Euonymus fortunei 'Emerald 'n' Gold'	Bushy; 9 breaks	N/A	5-7.5L	3/m²
188	Euo for S Q	Euonymus fortunei 'Silver Queen'	Bushy; 9 breaks	N/A	5-7.5L	3/m²
34	Euo for S	Euonymus fortunei 'Sunspot'	Bushy; 9 breaks	30-40cm	10L	4/m²
58	Euo jap B	Euonymus japonicus 'Bravo'.	Bushy; 4 breaks	40-60cm	5L	3/m²
304	Heb A G	Hebe 'Autumn Glory'	Bushy; 7 breaks	30-40cm	5L	3/m²
39	Heb R E	Hebe 'Red Edge'	Bushy; 7 breaks	N/A	5-7.5L	3/m²
103	Heb alb 'R E'	Hebe albicans 'Red Edge'	Bushy; 7 breaks	N/A	5-7.5L	4/m²
72	Heb bra W G	Hebe brachysiphon 'White Gem'	Bushy; 5 breaks	30-40cm	5L	3/m²
77	Heb rak	Hebe rakaiensis	Bushy; 7 breaks	N/A	5-7.5L	4/m²
86	Hyd mac W W	Hydrangea macrophylla 'White Wave'	Branched; 5 breaks	40-60cm	5L	3/m²
96	Hq	Hydrangea quercifolia	Branched; 3 breaks	40-60cm	5L	3/m²
129	Hyd ser B	Hydrangea serrata 'Bluebird'	Branched; 3 breaks	30-40cm	3L	3/m²
90	Ker jap	Kerria japonica	Branched; 5 breaks	40-60cm	3L	3/m²
58	Lav ang L P	Lavandula angustifolia 'Loddon Pink'	Bushy; 5 breaks	30-40cm	5-7.5L	3/m²
47	Lav ang M	Lavandula angustifolia 'Munstead'	Bushy; 7 breaks	30-40cm	5-7.5L	3/m²
42	Lav ang R	Lavandula angustifolia 'Rosea'	Bushy; 7 breaks	20-30cm	5L	4/m²
40	Leu wal R	Leucothoe walteri 'Rainbow'	Bushy; 5 breaks	30-40cm	5L	3/m²
31	Lon nit M G	Lonicera nitida 'May Green'	Bushy; 8 breaks	N/A	5L	3/m²
65	Nan dom F P	Nandina domestica 'Fire Power'	Bushy; 6 breaks	N/A	5L	4/m²
40	Phi B E	Philadelphus 'Belle Etoile'	Branched; 7 breaks	60-80cm	10L	3/m²
102	Pho fra L R R	Photinia fraseri 'Little Red Robin'	Bushy; 6 breaks	30-40cm	3L	3/m²
72	Pit ten T T	Pittosporum tenuifolium 'Tom Thumb'	Bushy; 3 breaks	10-20cm	5L	3/m²
178	Pru lau O L	Prunus laurocerasus 'Otto Luyken'	Bushy; 5 breaks	40-60cm	5-7.5L	3/m²
28	Ros off	Rosmarinus officinalis	Bushy; 5 breaks	40-60cm	5L	3/m²
18	Sar con	Sarcococca confusa	Bushy; 6 breaks	30-40cm	5L	3/m²
60	Sar hoo H	Sarcococca hookeriana humilis	Bushy; 7 breaks	25-30cm	7.5L	3/m²
128	Sar hoo d	Sarcococca hookeriana digyna	Bushy; 6 breaks	30-40cm	5L	3/m²
106	Ski con K G	Skimmia confusa 'Kew Green'	Bushy; 4 breaks	30-40cm	5L	3/m²
165	Ski jap R	Skimmia japonica 'Rubella'	Bushy; 4 breaks	30-40cm	5L	3/m²
86	Ski jap V	Skimmia japonica 'Veitchii'	Bushy; 4 breaks	30-40cm	5L	3/m²
49	Spi jap C L	Spiraea japonica 'Candle Light'	Bushy; 6/9 breaks	40-60cm	10L	3/m²
65	Spi jap G	Spiraea japonica 'Goldflame'	Bushy; 5/7 breaks	30-40cm	5-7.5L	3/m²
40	Vib dav	Viburnum davidii	Bushy; 4 breaks	30-40cm	5-7.5L	3/m²
23	Vib opu C	Viburnum opulus 'Compactum'	Bushy; 4 breaks	30-40cm	3L	4/m²
90	Vib pl M	Viburnum plicatum 'Mariesii'	Branched; 3 breaks	40-60cm	3L	3/m²
14	Vib tin E P	Viburnum tinus 'Eve Price'	Bushy; 5/7 breaks	40-60cm	7.5L	3/m²
78	Vin maj V	Vinca major 'Variegata'	Several shoots; 3 breaks	N/A	3L	3/m²
160	Vin min G J	Vinca minor 'Gertrude Jekyll'	Several shoots; 3 breaks		3L	4/m²
53	Wei flo F P	Weigela florida 'Foliis Purpureis'	Branched; 4 breaks	30-40cm	3L	4/m²

Total :3808

Herbaceous

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
81	Art P C	Artemisia 'Powis Castle'	Bushy; 5 breaks		3L	3/m²
50	Ast maj H B	Astrantia major 'Hadspen Blood'	Full Pot		2L	4/m²
66	Ber E M G	bergenia 'Eden's magic giant'	Full pot		1L	6/m²
103	Ber cor P	Bergenia cordifolia 'Purpurea'	Full pot		3L	3/m²
28	Cro E M	Crocosmia 'Emily McKenzie'	Full pot		2L	4/m²
28	Eup amy P	Euphorbia amygdaloides 'Purpurea'	Full pot		5L	3/m²
71	Ger J B	Geranium 'Johnson's Blue'	Full pot		2L	5/m²
67	Ger pha L L	Geranium phaeum 'Lily Lovell'	Full pot		1L	6/m²
37	Hem S	Hemerocallis 'Stafford'	Full Pot		3L	4/m²
48	Heu C	Heuchera 'Caramel'	Full Pot		3L	3/m²
37	Heu C	Heuchera 'Caramel'	Full Pot		3L	4/m²
28	Heu cyl G	Heuchera cylindrica 'Gisela"'	Full Pot		2L	3/m²
14	Heu mic P P	Heuchera micrantha 'Palace Purple'	Full Pot		5L	3/m²
35	Hos F	Hosta 'Francee'	Full Pot		2L	3/m²
66	Lam mac W N	Lamium maculatum 'White Nancy'	Full pot		1L	6/m²
58	Tia cor	Tiarella cordifolia	Full Pot		5L	3/m²

Total :837

Grasses

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
73	Bri med	Briza media	Full Pot; Sept to April planting; British native-origin		3L	4/m²
220	Car hac E	Carex hachijoensis 'Evergold'	Full Pot		5L	3/m²
102	Car mor I D	Carex morrowii 'Ice Dance'	Full pot		1-1.5L	6/m²
107	Car orn V	Carex ornithopoda 'Variegata'	Full Pot		3L	4/m²
55	Hak mac A	Hakonechloa macra 'Aureola'	Full Pot		5L	3/m²
102	Luz niv	Luzula nivea	Full pot		1-1.5L	6/m²
51	Sti aru	Stipa arundinacea	Full Pot		3L	4/m²
58	Sti ten P T	Stipa tenuissima 'Pony Tails'	Full Pot		5L	3/m²

Total :748

Conifers

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
65	Pin mug M	Pinus mugo 'Mops'	Bushy	10-20cm	3L	4/m²

Total :65

Hedges

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
500	Cor alb E	Cornus alba 'Elegantissima'	Branched; 4 breaks	60-80cm	5L	3.45Clr Double Staggered at 0.35m offset
1009	Euc D R	Escallonia 'Donard Radiance'	Bushy; 5 breaks	40-60cm	5L	3.45Clr Double Staggered at 0.3m offset
380	For int L	Forsythia intermedia 'Lynwood'	Branched; 5 breaks	60-80cm	5-7.5L	3.45Clr Double Staggered at 0.35m offset
369	Lig vul	Ligustrum vulgare	0/2; Cutting; branched; 3 breaks	60-80cm	BR	3.4Clr Double Staggered at 0.3m offset
380	Pho fra R R	Photinia fraseri 'Red Robin'	Branched; 6 breaks	40-60cm	5-7.5L	3.45Clr Double Staggered at 0.35m offset
273	Spi A	Spiraea 'Arguta'	Branched; 7 breaks	60-80cm	10L	3.45Clr Double Staggered at 0.3m offset

Total :2911

Native Hedge Mix

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
102	Ace cam	Acer campestre	1+2; Transplant - seed raised; BR	100-125cm		3.45Clr Double Staggered at 0.35m offset
102	Cor ave	Corylus avellana	1+2; Transplant - seed raised; branched; 4 breaks; BR	80-100cm		3.45Clr Double Staggered at 0.35m offset
405	Cra mon	Crataegus monogyna	1+2; Transplant - seed raised; BR	80-100cm		3.45Clr Double Staggered at 0.35m offset
102	Ile aqu	Ilex aquifolium	Leader with laterals	60-80cm	5L	3.45Clr Double Staggered at 0.35m offset
52	Ros can	Rosa canina	1+1; Transplant - seed raised; branched; 3 breaks; BR	60-80cm		3.45Clr Double Staggered at 0.35m offset
102	Cor san	Cornus sanguinea	1+1; Transplant - seed raised; branched; 4 breaks; BR	80-100cm		3.45Clr Double Staggered at 0.35m offset
52	Lon per	Lonicera periclymenum	C; 3/5 brks; Several Shoots; Cared	80-100cm	3L	3.45Clr Double Staggered at 0.35m offset
102	Que rob	Quercus robur	C; 3/5; Whip; Branched; 3/5 breaks			3.45Clr Double Staggered at 0.35m offset

Total :1019

Hedge Mix

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
107	Ber thu	Berberis thunbergii	1+2; Transplant - seed raised; branched; 3 breaks; BR	60-80cm	BR	3.45Clr Double Staggered at 0.35m offset
213	Car bet	Carpinus betulus	1+1; Transplant - seed raised; BR	60-80cm	BR	3.45Clr Double Staggered at 0.35m offset
248	Cor ave	Corylus avellana	1+2; Transplant - seed raised; branched; 3 breaks; BR	60-80cm	BR	3.45Clr Double Staggered at 0.35m offset
143	Pru pad	Prunus padus	1+1; Transplant - seed raised; BR	60-80cm	BR	3.45Clr Double Staggered at 0.35m offset

Total :711

Bulb Mix

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
212	Cro chr B P	Crocus chrysanthus 'Blue Pearl'	Grade 5/6			12/m²
212	Cro chr C B	Crocus chrysanthus 'Cream Beauty'	Grade 5/6			12/m²
212	Cro tom R G	Crocus tommasinianus 'Ruby Giant'	Grade 5/6			12/m²
281	Gal niv	Galanthus nivalis	Grade 5/6			12/m²
212	Nar tri	Narcissus 'triolet'	Grade 5/6			12/m²
212	Nar C	Narcissus 'Canaliculatus'	Grade 5/6			12/m²

Total :1410

© this drawing and the building works depicted are the copyright of **idp** and may not be reproduced or amended except by written permission. no liability will be accepted for amendments made by other persons.

all dimensions to be checked on site and landscape architect notified of any discrepancies prior to commencement.
do not scale.

NOTES:

1.0 Do not scale from drawing, use figured dimensions only
1.1 This drawing to be read in conjunction with all other IDPL drawings and specifications
1.2 Information shown on these drawings is not valid for Construction. Please refer to the status of the drawing in the Title and Issue box
1.3 Do not procure or manufacture materials, or undertake construction site works from this drawing unless the issue status is noted as 'for construction'.
1.4 Any contractor that chooses to take forward this information for construction without full review process and sign-off does so at their own risk.
1.5 All measurements are to be checked on site prior to construction
1.6 Where any conflict or inconsistency occurs between drawing and specification information the Contractor is to immediately notify IDPL prior to continuing working.
1.7 Information to be read in coordination with Structural Engineer & M&E Engineer drawings & spec; Where any conflict or inconsistency occurs between IDPL and Engineers drawing and specification information the Contractor is to immediately notify IDPL prior to continuing working.
1.8 Proposed drainage runs to be located within adoptable road carriageway and/or hardstanding where possible, please refer to separate drainage design.

PLANTING NOTES
General

1. All planting and operations should comply with the latest version of BS 4428 'General Landscape Operations' and BS 3936 'Nursery Stock - Specification for Trees & Shrubs'.
2. All plants shall be supplied in accordance with the HTA National Plant Specification and from a HTA certified nursery, and in accordance with CPSE Code of Practice for Handling and Establishing Landscape Plants, Parts I, II and III.
3. All existing trees and hedges shall be surveyed and protected in accordance with BS 5837:2012, and temporary protection fencing erected for the duration of the construction period. Refer to arboricultural consultants drawings for location and details.
4. Specification of species, position and density shall be in accordance with drawing and planting schedule provided, and should not be amended without prior approval of the Landscape Architect. For detailed landscape specification information, please refer to the relevant documentation accompanying this drawing.

Ground conditions/ Topsoil

5. All topsoil areas should be clear of rocks and rubble larger than 50mm diameter and any other debris that may interfere with the establishment of plants.
6. Imported topsoil to be multi-purpose grade and free of all contaminants, in accordance with the latest version of BS 3882:2015 Specification for Topsoil. Topsoil analysis should be undertaken and reported, with recommendations for improvements if below the standard for general landscape purposes.
7. Minimum topsoil depths should be as follows unless specified otherwise. Suitable (loosened) subsoil should provide the remainder of the rooting depths as required, and mixed with peat-free compost. Subsoil preparation shall be in accordance with BS 9001 and BS 4428 and scarified ripped to a suitable depth prior to spreading of topsoil. Any weed/grass growth to be sprayed with appropriate herbicide at least 10 days prior to cultivation.
   - Ornamental shrubs 450mm;
   - native shrubs 300mm;
   - seeded grass 150mm;
   - wildflower grass 50mm, or directly into existing ground;
   - tree pits to be excavated to at least twice the diameter of the root spread and 1.5 times the depth of the roots to be planted.

Cultivation

8. Planting outside the usual October-March dormant season shall be pursued by approval only. If agreed all bare root plants shall be substituted with container grown stock, with additional establishment watering.
9. Plants shall be bedded in random fashion to avoid formal regimented lines at densities indicated in the schedule, except for specimens, which are to planted in locations shown on the drawing. For shrubs, whole shrubs should be planted in blocks, perennials & grasses should be planted in groups of 3 to 5. Please note: taller plant species to be planted to the rear with lower species to the front.
10. All planting should be watered in to field capacity immediately after planting and mulched with minimum of 50mm depth of medium grade crushed mulch. Where necessary, plants to be protected with rabbit fence and/or individual rabbit guard securely fixed to timber stakes.

Trees & Foundations

11. All trees to be supplied, planted and established in accordance with BS 8545. Trees adjacent to buildings and services shall include root barriers where necessary and should be located in positions as indicated on the drawings.
12. All foundation designs provided by the architect/engineer must consider the effect of existing trees, and the proposed landscape scheme in accordance with the NHBC Standards. Every effort has been made within the design to follow advice in Chapter 4.2 of the Standards, however landscape proposals should be referred to a structural engineer for checks and any conflicts made known to the Landscape Architect for necessary changes.
13. The contractor is responsible for checking locations of all existing and proposed services, and shall advise the Landscape Architect if there are any conflicts.
14. Trees within hard/standing or highways visibility splays shall be clear stem to 2m high unless specified otherwise.

Maintenance

15. Management operations for the site shall be carried out as detailed in the agreed maintenance schedules at regular intervals, in accordance with any agreed Landscape Management Plan.
16. Any tree or plant which, within a period of 5 years from the implementation, dies, is removed or becomes seriously damaged or diseased, shall be replaced in the next planting season with another of a similar size and species unless otherwise agreed with the Local Planning Authority.

17. Tree Pits

18. Tree pits in soft areas only are estimated based on areas shown on plan multiplied by tree pit depth (0.9m) with allowances for wall foundations and kerb build ups as appropriate. Tree pits with supplementary root space soil cells are estimated based on areas shown on plan in soft areas multiplied by tree pit depth (1.135m) and areas under hard surfaces multiplied by soil cell depth (0.6m).

Application boundary

Existing vegetation retained

Lawn: Amenity
(Rolawn Medallion Grass)

Lawn: Flowering
(Emorsgate EG22 Strong Lawn Mixture; 25g/m2)

Meadow: Wildflower
(EM2 Standard General Purpose Meadow Mixture; 5g/m2)

Meadow: Woodland Edge
(Emorsgate EH1 - EH1 Hedgerow Mixture, 5g/m2)

Proposed trees

Proposed hedges

Proposed shrub planting

Proposed areas of gravel

rev.	date:	comment(s):	drawn:	check:
A	06.08.24	Retained / removed hedgerows amended	DM	EC

ARCHITECTURE
URBAN DESIGN & MASTERPLANNING
LANDSCAPE & ENVIRONMENT

status: Planning RIBA Stage: 4
client: Vistry Group
job: R6 R7 Woodlands, South Marston
title: Soft Landscape Proposals General Arrangement
drawn: DM date: 31.07.24
checked: EC scale @ a1: 1:500
drwg no: IDPL LA5979-BP-400 rev: A

IDP GROUP 27 SPON STREET COVENTRY CV1 3BA
T: **+44 (0)24 7652 7600** E:info@idpgroup.com
www.weareidp.com